

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24204

APPROVED SCHEDULE - B

NO. E/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements to roads, drains and construction of Culverts at Vinayaka Nagara internal roads and surrounding area in ward no 11

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				K ANIL KUMAR	
				In Figures	In Words
1	97.5	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces no exceeding 0.02 Cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 meters, stacking serviceable and unserviceable materials separately etc complete as per specifications and directions of engineer in charge of the work	Cum	822.0	Rupees Eight Hundred Twenty Two Only
2	357.21	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	192.0	Rupees One Hundred Ninety Two Only
3	126.87	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4500.0	Rupees Four Thousand Five Hundred Only
4	86.27	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	Rupees Five Thousand Only
5	699.6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	297.0	Rupees Two Hundred Ninety Seven Only
6	6.47	Providing T .M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	59327.0	Rupees Fifty Nine Thousand Three Hundred Twenty Seven Only
7	9	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- Data rate	sqm	5125.0	Rupees Five Thousand One Hundred Twenty Five Only
8	283.5	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- Data rate	Sqm	1760.0	Rupees One Thousand Seven Hundred Sixty Only

ಕಾರ್ಯಪಾಲಕ ಅಧೀಯಂತರರು

ಬ್ಯಾಟರಾಯನವರ ವಿಭಾಗ

ಪಿ.ಬಿ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

04/05




Signature of the contractor

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				K ANIL KUMAR	
				In Figures	In Words
9	81.25	Cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2M20/M30 at 380/450 kg per cum, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including leveling the form work as per drawing.), spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane, sealant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grade as per drawing complete as per specification M20 (at 300 kg per cum coarse aggregate @ 0.69 cum and fine aggregates @ 0.43 cum) etc complete as per specifications and directions of engineer in	Cum	5287.0	Rupees Five Thousand Two Hundred Eighty Seven Only
10	650	Vaccum De-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	97.0	Rupees Ninety Seven Only



Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
